Category 4

4.8 Open Project Estimate



The function of this window when setting up the project is reading project estimate from Fast Track.

1			_							_	_		_		_		_	_ 7
	Task Description			Act														
0	Mobilisation & Run			Α 🔨														
0 Condabri Temp Pwr Central to Nth Sth Gas Plants				A														
52 Condabri Water Gathering Cnt Nth & Sth 60 Control System (SCADA,Management)				A														
100 Condabri Electrical Wells Year 2012 Finish				A														
200	Condabri Electrical Wells \			AV														
				Announced Statistics														
_																		
k No	Catalogue Number	Description	Unit	Quantity	Price \$	Dis%	Ext Price \$	LabRt	ExtLab	M%	L%	Date Comp	Status	MatCC	LabCC	LabCArea	WgUnit	Wght S
0		Cable 185mm2 3C XLPE HD SCRN 11/11kV	m	300.00	80.33	1	24099.00	0.220	66.00	1	1			100	10	1		
Actual			m	1200.000	70.00	3.00	81480.00	0.150	180.00									
50		Cable 70mm2 3C XLPE HD SCRN 11/11kV	m	90.00	53.00		4770.00	0.300	27.00		-		-	100	10			
Actual				00000										(3332)	(Year)			
so		Terminations Pole Outdoor 185mm2 3 Core	ea	2.00	800.00		1600.00	8.000	16.00		_		-	10	1			
332		Terminauuris Pole Outdoor Tesmini2 3 Core	ea	2.00	000.00		1000.00	0.000	16.00									
Actual			_															
50		Terminations Indoor 185mm2 3 Core	ea	2.00	700.00		1400.00	6.000	12.00					10	1			
Actual											1							
50		Scissor Lifts 8 Metre	VWk	0.50	250.00		125.00	0.250	0.13					10	1		0	
Actual											1							
50		Terminations Indoor 70mm2 3 Core	ea	6.00	600.00		3600.00	6.000	36.00					10	1			
Actual			-								1							
50		High Pot Testing	Lot	1.00	850.00		850.00	8.000	8.00		-			10	1		-	
Actual			0.00	1.00				222206										
SO SO		Pole Protection Water Pipe	m	12.00	18.50		222.00	0.300	3.60					10	1			
		Fois Protection Water Plas		12.00	10.30		222.00	0.300	0.00									
Actual																		
50		Pole Protection Water Pipe Saddles	ea	8.00	12.00		96.00	0.250	2.00		1			10	1			
Actual																		
60		Section Name: - Main TrunskData Cabling																
Actual																		
60	BELD-NKGU62DA012BKB3	Cable Fibre Optic 12 Fibres	м	8500.00	13.20		112200.00	0.060	510.00									
Actual			ea	7500.000	15.30		114750.00	0.080	600.00	50.0	50.0							
2.549.5			1000		200 002 0	-	10000	020000	1000000	2000	2002							
								1										
<		III -								_		_						>
					Estimated Pric	e \$:-	148,962.00	-	680.73									
					Actual Pric	e \$:-	196,230.00	Act Hrs:-	780.00									
-		🖞 🕌 Import Fast Track	2								-	New	首, Ec		OK	XC		Clos

The estimate is working into "Kontrol Pro". When workings are read in this, users enable to track the difference of the Estimated Project and the Actual Project.

For example, if the estimate price for Motor Control Centre(MCC) was allowed at \$95,000.00, however the purchase price varied up or down. This gives users a clear indication of why and where the variation has happened. This also can give the user a very quick indication of the variance instead of getting to end of project and the accounts departments release the figures.

The other part of window is to go through and put the percentage complete instead of guessing. The window allows to put items in that may have been not allowed for.

If you are using Kontrol Pro Cable schedule and termination, do not extent the cables here. The same applies the equipment list.

📔 Import Fast Track

This button allows you to import a Fast Track estimate file.

Rebuilds complete current cable list. Defined by C= Current and H = Hold.

This prints the current screen to excel spread sheet.